



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

February 6, 1963

RECEIVED
STATE CORPORATION COMMISSION

FEB 14 1963 2-14-63

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Roy Pool of F. G. Holl has this

date requested permission to plug the following described well:

Mr. Pool guarantees payment of the plugging fee.

Operator's full Name: F. G. Holl

Complete Address: 6427 E. Kellogg, Wichita, Kansas

Lease Name: Schardein Well No. 1

Location: SW SW SE Sec. 29 Twp. 22 Rge. 7 (E) (W) X

County Reno Total Depth 3554 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pool was instructed to plug the well as follows:

Fill hole with sand to 3520' and cement with 3 sacks.

Fill hole with mud to 270'. Set rock bridge from 270' to

260' and cement with 20 sacks. Fill hole with mud to 40'.

Set rock bridge from 40' to 30' and cap hole with 10 sacks

cement.

Very truly yours,

Conservation Division Agent