

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
CONSERVATION DIVISION

11-3-66  
OCT 8 1966

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bill Rowe of Donald C. Slawson has this  
date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 408 One Twenty Bldg., Wichita, Kansas

Lease Name: Wells "A" Well No. # 1

Location: C SE NE Sec. 23 Twp. 24 Rge. 17 (E)(W)W

County Edwards Total Depth 4410' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

258' of 8 5/8" surface pipe, cement circulated. Fill hole with  
drilling mud to 240', 1st cementing plug, bridge with 1/2 sack of hulls,  
and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd  
cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks  
to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlene Elving  
Conservation Division Agent