



15-047-20720-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

JOHN CARLIN
R. C. LOUX
JANE T. ROY
WILLIAM G. GRAY
Carol J. Larson, Executive Secretary

Governor
Chairman
Commissioner
Commissioner

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Farmer of Big Springs Drlg., Inc. has this
date requested permission to plug the following described well:

8-25-80

Mr. Farmer guarantees payment of the plugging fee.
Operator's full Name: Arrowhead Pet., Inc.

RECEIVED
STATE CORPORATION COMMISSION

Complete Address: 400 N Woodlawn, Suite 29, Wichita, Ks. 67208

AUG 25 1980

Lease Name: Meyers Well No. 2

CONSERVATION DIVISION
Wichita, Kansas

Location: 100' N/C E $\frac{1}{2}$ E $\frac{1}{2}$ SE Sec. 33 Twp. 24s Rge. 16 (E)(W) W

County: Edwards Total Depth 3880 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole X

Mr. Farmer was instructed to plug the well as follows:
382' 8 5/8" casing w/275 sax cement. Set 60 sax cement plug
at 1080'--Bridge at 200' & 70 sax cement to top of casing.
Cemented by Allied. (Dakota water at 845' to 905')
Move rig 200' south. 10 sax in rat hole.

Very truly yours,

Conservation Division Agent