



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

7-27-72
RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Thompson of Sterling Drlg. Co. has this date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Holl-Sterling

Complete Address: 6427 E. Kellogg Wichita, Ks

Lease Name: Larimore Well No. 1

Location: SW/SW/SW Sec. 33 Twp. 24 Rge. 16 (E)(W) W

County: Edwards Total Depth 4477 Oil Well

Gas Well Input Well SWD Well D & A ~~Post Hole~~ Wash Down

Mr. Thompson was instructed to plug the well as follows:

306 ft 8 5/8 surface pipe cemented with 200 sacks. Fill
hole to 280 ft, plug, 1/2 sack hulls, 35 sacks cement. Mud
to 40 ft, plug, 1/2 sack hulls, 15 sacks cement to surface.
2 sacks cement in rat hole.

Very truly yours,

L. Russell B. Brinton
Conservation Division Agent