

API NUMBER 15-119-20951-0000

LEASE NAME Atkinson

WELL NUMBER 2-34

4620 Ft. from S Section Line

1520 Ft. from E Section Line

SEC. 34 TWP. 32 RGE. 29 (W) of (W)

COUNTY Meade

Date Well Completed 10/95

Plugging Commenced 1-11-2000

Plugging Completed 1-12-2000

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

FEB 16 2000

2-16-00

CONSERVATION DIVISION
 Wichita, Kansas

LEASE OPERATOR Kenneth S. White

ADDRESS 260 N. Rock Rd, Suite 240 Wichita KS

PHONE# (316) 618 9813 OPERATORS LICENSE NO. 30128

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-11-2000 (date)

By Gary Winters (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Lansing Depth to Top 4560 Bottom 4570 T.D. 5850

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>8 5/8</u>	<u>1531</u>	<u>-</u>
				<u>4 1/2</u>	<u>4922</u>	<u>3005</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mixed 1 SK hulls to 20 SX cmt. to plug perfs from 4560 to 4360.

Recovered 3005 4 1/2. Put 50 SX 1560 to 1410. 25 SX 700 to 600. 10 SX

40 to 0 Cut off & capped 8 3/8 6 ft. below G.L.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kenneth S. White

STATE OF Kansas COUNTY OF Sedgwick, ss.

Kenneth S. White

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kenneth S. White

(Address) 260 N. Rock Road, Ste 240 Wichita KS 67206

SUBSCRIBED AND SWORN TO before me this 15th day of February, 2000

Susan M. Way

Notary Public

My Commission Expires

