

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ford County, Sec. 26 Twp. 27-S Rge. (E) 24 (W)

Location as "NE/CNW%SW%" or footage from lines NE SE SW

Lease Owner Tennessee Gas Transmission Company

Lease Name Loren L. Barngrover Well No. 1

Office Address P. O. Box 163 - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Lost Hole

Date well completed _____ 19____

Application for plugging filed February 23, 19 60

Application for plugging approved February 23, 19 60

Plugging commenced February 23, 19 60


Plugging completed February 23, 19 60

Reason for abandonment of well or producing formation _____

Lost hole @ 2661'

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Frank Broadfeet

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2661 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1527.79	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

15 sacks cement set @ 300', mudded to 40', 10 sacks cement from 40' to surface.

RECEIVED
STATE CORPORATION COMMISSION
MAR 1 1960
CONSERVATION DIVISION
Wichita, Kansas
3-1-1960

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones Drilling Company

Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Glen E. Armour (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen E. Armour

P. O. Box 163 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of February, 19 60

John Linn
Notary Public.

My commission expires October 13, 1962

GABBERT-JONES DRILLING CO., INC.
WICHITA, KANSAS
DRILLER'S WELL LOG

LOREN L. BARNGROVER #1
 NE SE SW SECTION 26-27S-24W
 FORD COUNTY, KANSAS

COMMENCED: FEBRUARY 10, 1960
 COMPLETED: FEBRUARY 24, 1960

OPERATOR- TENNESSEE GAS AND OIL COMPANY

DEPTH		FORMATION	REMARKS
0	134	SAND AND SHALE	<p>RECEIVED STATE CORPORATION COMMISSION</p> <p>APR 12 1963</p> <p>CONSERVATION DIVISION Wichita, Kansas</p> <p>RAN 1558' OF 8-5/8" CASING, CEMENTED @ 1531' W/900 SACKS CEMENT.</p> <p>HOLE ABANDONED</p>
134	215	SAND	
215	397	SHALE, SHELLS & SAND	
397	451	SAND	
451	620	SHALE	
620	1020	SHALE & SHELLS	
1020	1045	RED BED	
1045	1190	SHALE & SHELLS	
1190	1245	SHALE, SHELLS & RED BED	
1245	1365	RED BED, SHALE & ANHYDRITE	
1365	1515	SHALE, SHELLS & ANHYDRITE	
1515	1532	ANHYDRITE	
1532	1555	ANHYDRITE & SHALE	
1555	1795	SHALE, SHELLS & RED BED	
1795	1990	LIME & SHALE	
1990	2225	SALT, LIME & SHALE	
2225	2565	LIME & SHALE	
2565	2630	LIME, DOLOMITE & SHALE	
2630	2663	LIME & DOLOMITE	
2663	TD		

I, E. E. HALL, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S WELL LOG FOR THE LOREN L. BARNGROVER #1.


E. E. Hall
 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 11TH DAY OF MARCH, 1960, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND DATE LAST ABOVE WRITTEN.

Vira A. McKenzie
 VIRA A. MCKENZIE, NOTARY PUBLIC



My Commission Expires OCTOBER 2, 1963