

RECEIVED

Notice: Fill out COMPLETE and return to Conservation Division at the address below within 30 days from plugging date

OCT 09 2003
KCC WICHITA
10-9-03

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Eagle Creek Corporation

Address: 150 N Main #905-Wichita, KS 67202

Phone: (316) 264-8044 Operator License #: 30129

Type of Well: Oil Docket #: N/A
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 09/16/03 (Date)

by: Mike Meyer (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
Morrow Depth to Top: 5540' Bottom: 5544' T.D. 6103'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-119-20924 ~~100-00~~

Lease Name: Fox

Well Number: 1-22

Spot Location (QQQQ): W/2 - NW - SE

1980 Feet from North / South Section Line

2310 Feet from East / West Section Line

Sec. 22 Twp. 32 S. R. 30 East West

County: Meade

Date Well Completed: _____

Plugging Commenced: 09/17/03

Plugging Completed: 09/18/03

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Morrow</u>	<u>Oil</u>	<u>5540'</u>	<u>5544'</u>	<u>20"</u>	<u>56'</u>	<u>0</u>
				<u>8 5/8"</u>	<u>1627'</u>	<u>0</u>
				<u>4 1/2"</u>	<u>6067'</u>	<u>2810'</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Placed plugs as follows: 20 sks of cement, 100# of hulls from 5544' to 5400', 50 sks of cement from 1650' to 1450', 40 sks of cement from 550' to 390', 10 sks of cement from 40' to 0' with mud spacing each plug

Name of Plugging Contractor: Sargent & Lillard Casing Pulling, Inc License #: 32833

Address: PO Box 1450-Woodward, OK 73802-1450

Name of Party Responsible for Plugging Fees: EAGLE CREEK CORPORATION

State of KANSAS County, SEDOGWICK, ss.

DAVE CALLEWAERT (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 150 N. MAIN SUITE 905 WICHITA, KS 67202

SUBSCRIBED and SWORN TO before me this 8th day of OCTOBER, 20 03

[Signature] My Commission Expires: 4/28/05
Notary Public

Debora R. Haddock

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 [initials]

