



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 8 1963

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Hicks of Petroleum Inc. has this  
 date requested permission to plug the following described well:

Mr. Hicks guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 352 North Broadway, Wichita, Kansas

Lease Name: Strecker Well No. D-1

Location: NE/4 SW/4 Sec. 9 Twp. 24 Rge. 21 (E) (W)

County Hodgeman Total Depth 4699 Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Hicks was instructed to plug the well as follows:

8 5/8"-258' Circulated w/cement.

Mud 4699' to 540' 20 Sax. cement spotted 540' to 480'

Mud 480' to 240' 20 Sax. cement spotted 240' to 180'

Mud 180' to 40' Plug, HULLS, 15 Sax. cement 40' to surface.

Very truly yours,

*[Signature]*  
 Conservation Division Agent