



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 3-3-64
 MAR 3 1964

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Blevins of Jones - Gebert Oil Inc. has this date requested permission to plug the following described well:

Mr. Blevins guarantees payment of the plugging fee.

Operator's full Name: Jones - Gebert Oil Inc.

Complete Address: 205 Central Bldg. Wichita, Kansas

Lease Name: Schartz Well No. 1

Location: C NW NE Sec. 9 Twp. 24S Rge. (E) (W) 21

County Hodgeman Total Depth 4770' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Blevins was instructed to plug the well as follows:

8 5/8"-220' Circulated w/cement.
Mud 4770' to 700' Spotted 25 Sax.cement 700' to 625'
Mud 625' to 220' Spotted 25 Sax.cement 220' to 145'
Mud 145' to 40' Plug.Hulls, 15 Sax.cement 40' to 0

Very truly yours,

[Signature]
 Conservation Division Agent