

15-083-10068-0000

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 16 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Unruh of Bovaird Supply Co. has this
date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Bovaird Supply Company

Complete Address: Box 897, Great Bend, Kansas

Lease Name: Strecker "A" Well No. 3

Location: C SW NW Sec. 9 Twp. 24 Rge. 21 (X) (W)

County Hodgemah Total Depth 4677' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Unruh was instructed to plug the well as follows:

8 5/8" to 234' circulated w/ cement. 4 1/2" to 4675' cemented.

No Perforations. Plug Bottom w/ 75' of sand & "40" Sacks cement

Top of cement 4550' Mud 4550' to 285'

Plug & 40 sacks Cement 285' to 165' Mud 165' to 30'

Plug Top w/ 10 sacks of cement 30' to 0. Weld Plate on 8 5/8".
Pump.

Very truly yours,

Edgar J. Eves
Conservation Division Agent