



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 2 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202


Dear Sir:

Mr. Sullivan of Pickrell has this

date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.Operator's full Name: Pickrell Drilling Co.Complete Address: 705 4th Nat'l Bk. Bldg., Wichita, KansasLease Name: Ø/A/2/NW/NW Gleason "C" Well No. 1Location: C N/2 NW NW Sec. 5 Twp. 24 Rge. 21 (E)(W)County: Hodgeman Total Depth 4665' Oil Well XGas Well      Input Well      SWD Well      D & A X Lost Hole     Mr. Sullivan was instructed to plug the well as follows:8 5/8" to 260' circulated w/ cement. 5 1/2" to 4650' cemented.Top perforations 4432' Plug bottom w/ sand & 5 sacks cementTop of cement 4350' Mud 4350' to 850'Spott 80 sacks cement 850' to 550' Mud 550' to 260'Spot 30 sacks cement 260' to 160' Mud 160' to 40'Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

  
Conservation Division Agent