

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

JUL 5 1966

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Pulley of Colo. Oil Co. has this

date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Colorado Oil Company

Complete Address: 915 Union National Building, Wichita, Kansas

Lease Name: Burke "A" Well No. 1

Location: C SE SW Sec. 4 Twp. 24 Rge. 21 (E) (W)

County Hodgeman Total Depth 4753' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pulley was instructed to plug the well as follows:

8 5/8" to 251' circulated w/ cement. 5 1/2" to 4752' cemented

Top of perforations 4727' Plug bottom w/ 20 sacks cement.

Top of cement 4600' Mud 4600' to 700'

Plug & 30 sacks cement 700' to 600' Mud 600' to 300'

Spotted 35 sacks cement 300' to 200' Mud 200' to 45'

Plug, Hulls & 13 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent