



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 14 1964
1-14-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Blevins of Jones-Gebert Oil Inc. has this date requested permission to plug the following described well:

Mr. Blevins guarantees payment of the plugging fee.

Operator's full Name: Jones-Gebert Oil Inc.

Complete Address: 205 Central Bldg. Wichita, Kansas

Lease Name: Hogan Well No. 1

Location: C SW NE Sec. 24 Twp. 24 Rge. (E) (W) 22

County Hodeman Total Depth 4900' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Blevins was instructed to plug the well as follows:

8 5/8"-235' Circulated w/cement.

Mud 4900' to 600' Spotted 25 Sax.cement 600' to 525'

Mud 525' to 215' Spotted 25 Sax.cement 215' to 140'

Mud 140' to 40' Plug, HULLS, 10 Sax.cement 40' to 0

Very truly yours,

Conservation Division Agent