



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

October 7, 1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

10-11-68
RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1968
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Ralph Glenn of Glenn & Smith Pipe Pulling Co. has this date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Alpine Oil and Royalty Company, Inc.

Complete Address: 800 Bitting Bldg., Wichita, Kansas 67202

Lease Name: Janzen Well No. 1

Location: SE NW SW Sec. 7 Twp. 22 Rge. 4 (E) (W) XX

County: Reno Total Depth 3881' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Glenn was instructed to plug the well as follows:

Fill hole with sand to 3850' and cement with 5 sacks.

Fill hole with mud to 260'. Set rock bridge from 260' to 250' and

cement hole with 25 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent