

State of Kansas



15-155-20423-0000  
FORM CP-2

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water  
WICHITA, KANSAS 67202

May 19, 1977

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 25 1977  
5-25-77  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Herb French of Pickrell Drilling Co. has this date requested permission to plug the following described well:

Mr. French guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 205 Litwin Bldg., Wichita, Kansas

Lease Name: Franz "C" Well No. 1

Location: 150' W of C NW SE Sec. 15 Twp. 22 Rge. 4 (E) (W) X


County: Reno Total Depth 3890' Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. French was instructed to plug the well as follows:

Fill hole with mud. Pump 35 sacks cement through drill pipe  
at 300'. Push plug and 1/2 sack hulls to 40' and cap hole with  
40 sacks cement. Bridge rathole and cement with 2 sacks  
cement.

Very truly yours,

  
Conservation Division Agent