



15-155-20040-0000

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg.
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1968
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

January 5, 1968

1-11-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ross Crawford of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Mr. Crawford guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Inc.

Complete Address: 1515 Wichita Plaza, Wichita, Kansas 67202

Lease Name: Nelson Well No. 1

Location: NE SE NE Sec. 34 Twp. 22 Rge. 6 (E) (W) X

County: Reno Total Depth 4061' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crawford was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/4 sack hulls to 200' and
cement hole with 25 sacks through drill pipe. Fill hole with mud to
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent