

KANSAS

FORM CP-3  
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- (none)

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name F.G. HOLL

Complete Address 6427 EAST HELLOGG, WICHITA, KANS. 67207

Lease Name WHITE Well No. # 1-7

Location 440' FNL-440' FEL-NE Sec. 7 Twp. 24 Rge. 17 (East) (West)

County EDWARDS Total Depth 4492 FT.

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor HELSO CASING PULLING

Address BOX 176 CHASE, MO. License No. 683

Operation Completed: Hour: 2:15 PM Day: 7<sup>th</sup> Month: AUG. Year: 1981

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

8 5/8" - 259 FT. SD. CUL. w/ 225 ST. → 4 1/2" SET @ 4492 FT. w/ 150 ST. CMT.  
PLUG. BACK T.O. 4455 FT. → TOP PERFS. 4396 FT. TO 4398 FT.  
SAND BOTTOM TO 4350 FT. w/ 4 ST. CMT. → SHUT 7 TIMES, - RECOVERED 2815 FT.  
ORDERED 125 ST. 50% PREMIX 4% GEL. + 3% CA-CL. → 25 ST. GEL. → 6 HULLS. + 8 5/8" PLUG.  
PUMPED IN 8 5/8" WITH PUMP TRUCK.  
PAT IN - 15 ST. GEL. → 6 ST. HULLS. → 10 ST. GEL. → RELEASED PLUG.  
AND 125 ST. CMT. MAX. PRESSURE 450 LBS

CEMENTED BY ALLIED CMT.

RECEIVED  
STATE CORPORATION COMMISSION  
8-11-81

I hereby certify that the above well was plugged as herein stated.

Signed: Marion Shriest  
Conservation Division Agent

INVOICED  
CONSERVATION DIVISION  
Wichita, Kansas

DATE 9-28-81

INV. NO. 7594-W