

VP
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
11-9-65
NOV 9 1965
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name Barber Well No. 1

Location C NW NE Sec. 20 Twp. 22 Rge. 8 (E) (W) X

County Reno Total Depth 3605'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 1 PM Day 6 Month November Year 1965

The Above well was plugged as follows:

4 1/2" plug pushed to 3540'. Hole filled with sand to 3530' and cemented
with 3 sacks. Hole bailed to 210'. Rock bridge set from 210' to 200'
and hole cemented with 22 sacks. Hole filled with mud to 40'. Rock bridge
set from 40' to 30' and hole cemented to base of cellar with 10 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 11/9/65
INV. NO. 2135-11

Signed: *William J. Lomen*
Well Plugging Supervisor