

KANSAS

Form CP-3
Rev. 6-4-68STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202API Number 15 - 155 - 20534 (of this well)

Operator's Full Name Barnett Oil, Inc.

Complete Address 1625 Vickers-KSB&T Bldg., Wichita, Kansas 67202

Lease Name Drake Well No. 1

Location C NE SW Sec. 5 Twp. 22 Rge. 9 (E) (W) X

County Reno Total Depth 3655'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Sterling Drilling Company and Allied Cementing Co.

Address Box 129, Sterling, Kansas License No.

Operation Completed: Hour 8:30 AM Day 13 Month July Year 1978

The above well was plugged as follows:

Hole filled with mud. 40 sacks cement pumped through drill pipe at 500'.

25 sacks cement pumped through drill pipe at 210'. Plug and $\frac{1}{2}$ sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement.

Rathole bridged and cemented with 2 sacks cement.

8-5/8" surface casing set at 222'--cement circulated.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed [Signature]
Well Plugging SupervisorDATE 7-25-78INV. NO. 2732-W