

1 120484

10-10

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-21,061-0000

N/2 N/2 NW, SEC. 1, T 24 S, R 18 WXK

4950 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name White Well # 2-1

Operator: F.G. Holl Company

County Edwards 148.68

Name & Address P.O. Box 780167

Well Total Depth 4575 feet

Wichita, KS 67278

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 10 Month: 10 Year: 19 90

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4567' w/225 sx cement, PBSD 4525', Perfs at 4372-78'

1st plug pump 1 sx hulls and 20 sx common cement,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4 p.m. Day: 10 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped into 4 1/2" casing with 100 lbs. hulls, 50 sx cement to 3600',

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-600 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2800' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE OCT 23 1990

10-17-90 OCT 17 1990 Signed

Steve Durrant (TECHNICIAN)

INV. NO. 29696

CONSERVATION DIVISION Wichita, Kansas

FORM CP-2/3 Rev. 01-84