

3-24-88

To: 1 061083
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,439-0000

NE NE NW, SEC. 24, T 24 S, R 18 W/E
4840 feet from S section line
3080 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056
Operator: F.G. Holl Company
Name & Address 6427 East Kellogg
P.O. Box 780167
Wichita, KS 67207

Lease Name Cross Well # 2-24
County Edwards 149.63
Well Total Depth 4604 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:40 p.m. Day: 24 Month: 3 Year: 19 88

Plugging proposal received from Dallas Fulls

(company name) Kelso Casing Pulling (phone) 316-928-2457

were: 4 1/2" at 4600' PBD 4584' Perfs at 4425-29'

1st plug sand back to 4375' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:40 p.m. Day: 24 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4375' and dumped 4 sx cement on top of
sand through bailer.

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released
8 5/8" wiper plug and pumped 130 sx cement.

Maximum pressure 750 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2000' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 3-29-88
INV. NO. 20241

Signed Paul A. Luthi
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAR 28 1988
CONSERVATION DIVISION
Wichita, Kansas

3-28-88