

1080296

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,917 - 0000

TECHNICIAN'S PLUGGING REPORT

SW SW , SEC. 23, T 24 S, R 18 W/E

330 feet from S section line

4950 feet from E section line

Operator License # 5151

Lease Name McClaren Well # 1

Operator: Gear Petroleum Co., Inc.

County Edwards 152.10

Name & Address 300 Sutton Place

Well Total Depth 4680 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 836

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 pm Day: 31 Month: December Year: 19 84

Plugging proposal received from Clay Duntz

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4583' PBTD 4551' Perfs at 4463-65'

1st plug pump 20 sx cement to bottom and stop plug at 4400'

2nd plug squeeze well with 3 sx hulls, 9 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 100 sx cement

Plugging Proposal Received by Richard W. Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:20 pm Day: 31 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4583' PBTD 4551' Perfs at 4463-65'

1st plug pumped 20 sx cement to bottom and stopped plug at 4400', 2nd plug pumped

3 sx hulls, 9 sx gel, and well pressured up to 1500 psi, so pumped 170 sx cement.

Shut in pressure 1500 psi

RECEIVED
STATE CORPORATION COMMISSION

JAN 07 1985
1-7-85

CONSERVATION DIVISION

Remarks: Recovered 2900' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% ~~Wichita, Kansas~~

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed J. A. [Signature]
(TECHNICIAN)

DATE 1-14-85

INV. NO. 6415