

1 080295

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,987-0000 *R*

NW NW SW, SEC. 23, T 24 S, R 18 W/EX
2310 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Fox Well # 1-23

Operator: Gear Petroleum Co., Inc.

County Edwards 151.13

Name & Address 300 Sutton Place

Well Total Depth 4650 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 817 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 31 Month: December Year: 19 84

Plugging proposal received from Clay Duntz

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4648' PBTD 4596' Perfs at 4473-79'

1st plug pump 20 sx cement to bottom and stop plug at 4400'

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00 am Day: 31 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4648' PBTD 4596' Perfs at 4473-79'

1st plug pumped 20 sx cement to bottom and stopped plug at 4400', 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
1-7-85
JAN 07 1985

Maximum pressure 500 psi and shut in 50 psi

Remarks: Recovered 2500' 4 1/2" casing. Used 60/40 Pozmix 2% gel 13% mica. *As Allied.*
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

INVOICED
DATE 1-14-85
INV. NO. 6416

Signed *J. H. Metz*
(TECHNICIAN)