

To: 1121020
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #D-22,390-0000

N/2 SW SW, SEC. 23, T 24 S, R 18 W/E

990 feet from S section line

4620 feet from E section line

Lease Name Fox Well # 2-23

County Edwards

Well Total Depth 4620 150.15 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 842

TECHNICIAN'S PLUGGING REPORT

Operator License # 30436

Operator: Dallas Production Inc.

Name & Address 4600 Greenville Ave.

Dallas, TX 75206-5038

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Dallas Production Inc. License Number 30436

Address 4600 Greenville Ave., Dallas, TX 75206-5038

Company to plug at: Hour: 9:30 a.m. Day: 23 Month: 2 Year: 1995

Plugging proposal received from Archie Crawford

(company name) Dallas Production Inc. (phone) 1-800-531-2724

were: 4 1/2" at 4613', TOC 4000', Perfs at 4520-44'

1st plug fill 4 1/2" casing with cement,

2nd plug pump cement to 900' in 8 5/8" X 4 1/2" annulus.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11 a.m. Day: 23 Month: 2 Year: 1995

ACTUAL PLUGGING REPORT 1st plug pumped in 4 1/2" casing with 250 lbs. hulls and 210 sx cement. Pumping pressure 0-800 psi and shut in 300 psi.

2nd plug pumped in 4 1/2" X 8 5/8" annulus with 150 lbs. hulls and 150 sx cement.

Pumping pressure 0-800 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 8% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED
(I, the undersigned) observe this plugging.

DATE 3-6-95

INV. NO. 42327

2-23

Signed Duane Rankin (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION MAR 01 1995 CONSERVATION DIVISION WICHITA, KANSAS