

1030234

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,969 - 0000

NE NE SE, SEC. 22, T 24 S, R 18 W/E
2310 ^{FSV} feet from N SE Corner of NXX section line
330 ^{FEV} feet from W SE Corner of NXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5021

Lease Name Pratt Well # 1-22

Operator: Imperial Oil Company

County Edwards

Name & Address 720 Fourth Financial Center

Well Total Depth 4430 143.98 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 604

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 1 Month: August Year: 19 84

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4429' Perfs 4334-4324' PBTB 4380'

1st plug sand back to 4270' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 150 sx cement

Plugging Proposal Received by Steve O'Connell
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:15 pm Day: 1 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4429' Perfs 4334-4324' PBTB 4380'

1st plug sanded back to 4270' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 150 sx cement.

Maximum pressure 450 psi and shut in pressure 250 psi

Remarks: They recovered 3016' of 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 8-17-84

AUG 06 1984
8-6-84

Signed Steve O'Connell
(TECHNICIAN)

INV. NO. 3201

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84