

1 030163

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,014 - 0000

C NE NE, SEC. 22, T 24 S, R 18 W/E

\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5021

Lease Name Knudson Well # 2-22

Operator: Imperial Oil Company

County Edwards

Name & Address 720 Fourth Financial Center

Well Total Depth 4632 150.54 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 608

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 24 Month: April Year: 19 84

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2 set at 4631 PBTD 4250' Perfs 4043-45 4178-80

1st plug sand back to 3975 and dump 4 sx cement on top of sand

2nd plug squeeze well with 3 sx hulls, 20 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump an additional 150 sx cement.

Maximum pressure 300# and shut in pressure 200#

Plugging Proposal Received by Steve Dumont  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 am Day: 24 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4631 PBTD 4250 Perfs 4043-45 4178-80

1st plug sand back to 3975' and dump 4 sx cement on top of sand, 2nd plug squeeze well

with 3 sx hulls, 20 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber

plug and pump an additional 150 sx cement.

Maximum pressure 300# and shut in pressure 200#

Remarks: They recovered 3579' of 4 1/2" casing. Use 60/40 Pozmix 2% gel 3% cc by Halliburton  
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 5-4-84

MAY 03 1984

Signed Steve Dumont  
(TECHNICIAN)

INV. NO. 1386

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84