

To: 1 051283
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-2015-083-10067-573
API NUMBER 15- 10-2-63

NE NW, SEC. 9, T 24 S, R 21 W/E

4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5266

Lease Name Strecker "A" Well # 2

Operator: K+E Drilling Inc
Name &

County Hodgeman 153.73

Address 100 S. Main

Well Total Depth 4730 feet

Suite 300

Conductor Pipe: Size _____ feet

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 205

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Well Service License Number 6454

Address P.O. Box 384 Ness City KS 67560

Company to plug at: Hour: 9:00 am Day: 15 Month: March Year: 1990

Plugging proposal received from Al Hammersmith

(company name) K+E Drilling (phone) 316-792-2729

were: 4 1/2 casing @ 4729' PBTD 4690' Perfs @ 4650-54

1st plug sand back to 4600' + spot 10sx cement on top

through tubing. Perforate 4 1/2" casing @ 1000'. Run tubing

to 1110' + circulate cement to O. 3rd plug pump

100sx cement down 8 5/8" x 4 1/2" annulus

Plugging Proposal Received by Steve Parrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:30 am Day: 20 Month: March Year: 1990

ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' + spotted 10sx

cement on top through tubing. 2nd plug perforated 4 1/2"

casing @ 1000' Run tubing to 1110' + circulated cement

to surface using 150sx of cement. 3rd plug pumped 80sx

cement down the 8 5/8" x 4 1/2" annulus. Cement inside 4 1/2"

tell to 150'. On 3-20-90 filled 4 1/2" to surface with redi mix

Remarks: Used 60/40 pozmix 6% gel by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 4-5-90

INV. NO. 27790

APR 02 1990 4-2-90 Signed Richard W. Lacey
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas