

3-2015-083-100691430

1 051282

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 10-18-63
NW NW, SEC. 9, T 24 S, R 21 W/4

4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5266

Lease Name Strecker "A" Well # 4

Operator: K+E Drilling Inc.
Name & Address: 100 S. Main
Suite 300
Wichita, KS 67202

County: Hodgeman 153.56
Well Total Depth 4725 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 206

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Well Service Inc License Number 6454

Address P.O. Box 384 Ness City, KS 67560

Company to plug at: Hour: 9:00 Day: 15 Month: March Year: 1990

Plugging proposal received from Al Hammersmith

(company name) K+E Drilling (phone) 316-792-2729

were: 4 1/2 @ 4724 PBD 4530 Perts @ 4434-4440 4450-4460

1st plug sand back to 4375' and spot 10sx cement on top through tubing. 2nd plug: circulate cement through tubing from 1470' to 0'. 3rd plug pump 100sx cement down 8 5/8" x 4 1/2" annulus

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:00a Day: 20 Month: March Year: 1990

ACTUAL PLUGGING REPORT 1st plug sanded back to 4375 and spotted 10sx cement on top through tubing. 2nd plug circulated cement from 1470' to 0' through tubing using 200 sx cement 3rd plug pumped 85sx cement down 8 5/8" x 4 1/2" annulus. Cement inside the 4 1/2" casing fell to 570'. On 3-20-90 The hole was topped off from 570 to 0 with redimix

Remarks: Used 60/40 permix 6% gel by Halliburton. 4 1/2 casing had holes from 1400 to 600' (If additional description is necessary, use BACK of this form.)

INVOICED (I did not observe this plugging.)

DATE 4-5-90 APR 02 1990 4-2-90

Signed Richard M. Lacy (TECHNICIAN)

INV. NO. 27791

CONSERVATION DIVISION
Wichita, Kansas