

1 120157
To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Operator: L.D. Drilling, Inc.

Name & Address Route 1, Box 183-B

Great Bend, KS 67530

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒ X

Other well as hereinafter indicated ☐

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address Route 1, Box 183-B, Great Bend, KS 67530

Company to plug at: Hour: 9:20 a.m. Day: 28 Month: 10 Year: 19 88

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1478-1510'

1st plug at 1510' with 50 sx cement, 2nd plug at 750' with 30 sx cement,

3rd plug at 460' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☐ Part ☒ X None ☐

Operations Completed: Hour: 11 a.m. Day: 28 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1510' with 50 sx cement,

2nd plug at 750' with 30 sx cement,

3rd plug at 460' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby acknowledge and observe this plugging.

DATE 11-7-88

INV. NO. 22913
10-28

Signed Paul Luthi
(TECHNICIAN)