

1070467

11-12-87

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-083-20,841-0000

SW <sup>NW</sup> NE SE, SEC. 5, T 24 S, R 21 W ~~EX~~

1650 feet from S section line

990 feet from E section line

Lease Name Gleason "B" Well # 1

County Hodgeman 155.84

Well Total Depth 4795 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 614

TECHNICIAN'S PLUGGING REPORT

Operator License # 8914

Operator: H & C Oil Operating, Inc.

Name & Address P.O. Box 86

Plainville, KS 67663

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor H & C Oil Operating, Inc. License Number 8914

Address P.O. Box 86, Plainville, KS 67663

Company to plug at: Hour: 11:30 a.m. Day: 12 Month: 11 Year: 1987

Plugging proposal received from Bob Plant

(company name) H & C Oil Operating, Inc. (phone) 913-434-7434

were: 4 1/2" at 4803' PBSD 4640' Perfs at 4491-4630' Elevation 2365' GL

1st plug sand back to 4440' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls and 125 sx ATL cement.

Plugging Proposal Received by Dan Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12 p.m. Day: 12 Month: 11 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 4440' and dumped 6 sx cement on top of sand through bailer,

11-17-87

2nd plug pumped 400 lbs. hulls and 125 sx ATL cement.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 17 1987

Maximum pressure 700 psi and shut in 400 psi.

CONSERVATION DIVISION  
Wichita Kansas

Remarks: Used ATL cement by Allied. Recovered 2123' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  Preserve this plugging.

Signed Dan Goodrow (TECHNICIAN)

DATE NOV 20 1987

INV. NO. 18905

11-12