

1031553

TO: STATE CORPORATION COMMISSION

API NUMBER 15-083-20,753-0000
SE NE SW SEC. 5, T 24 S, R 21 W

CONSERVATION DIVISION - PLUGGING SECTION 1720 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME VIRGINIA GLEASON WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY HODGEMAN 155.97

OPERATOR LICENSE # 8914

WELL TOTAL DEPTH 4799 FEET

OPERATOR: H & C OIL OPERATING, INC. PRODUCTION CSG: SIZE 5 1/2" @ 4799' WITH 200 SX

NAME AND PO BOX 86 SURFACE CASING: SIZE 8 5/8" @ 550' WITH 350 SX

ADDRESS PLAINVILLE, KS 67663

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR GOLDEN OIL LICENSE NUMBER 32627

ADDRESS PO BOX 861 HAYS, KS 67601

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 15 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RON GEIST

(COMPANY NAME) GOLDEN OIL (PHONE) 785-650-1365

WERE: PERFS AT 4689-92, 4670-72

1ST PLUG PUMP 5 SX GEL, 50 SX CEMENT, AND DISPLACED WITH 5 SX GEL AT 1400'. 2ND PLUG

AT 580' WITH 50 SX CEMENT. 3RD PLUG AT 40-0' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 2:40 PM DAY: 15 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT _____

1ST PLUG PUMP 5 SX GEL, 50 SX CEMENT AND DISPLACED WITH 5 SX GEL AT 1400'. 2ND PLUG AT

580' WITH 50 SX CEMENT. 3RD PLUG AT 40-0' WITH 10 SX CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

JUN 19 2000

CONSERVATION DIVISION
Wichita, Kansas

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2410' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

SIGNED STEVE DURRANT SA
(TECHNICIAN) FORM CP-2/3

DATE 6/21/00

INV. NO. 61884

(R)