

1 030954

6-9-88

API NUMBER 15-083-21,234 - 0000

C NE SW, SEC. 4, T 24 S, R 21 WYB

1980 feet from S section line

3300 feet from E section line

Lease Name Burke Well # 1

County Hodgeman 152.69

Well Total Depth 4698 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 302

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Operator: Edmiston Oil Company, Inc.
Name & Address: 1260 Kansas State Bank Bldg.
Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, KS 67524

Company to plug at: Hour: 1:40 p.m. Day: 9 Month: 6 Year: 19 88

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4685' PBD 4542' Perfs at 4461-65'

1st plug sand back to 4410' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 12 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:15 p.m. Day: 9 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4410' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 12 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JUN 24 1988 6-24-88

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2940' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed S. Durrant (TECHNICIAN)

DATE 6-30-88

INV. NO. 21154