

1041414

TO: STATE CORPORATION COMMISSION

API NUMBER 15-083-21,466-0000
NE SE NE SEC. 4, T 24 S, R 21 W

CONSERVATION DIVISION - PLUGGING SECTION 3630 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME GLEASON WELL # 1

TECHNICIAN'S PLUGGING REPORT

8/30

COUNTY HODGEMAN 149.27

OPERATOR LICENSE # 31191

WELL TOTAL DEPTH 4593 FEET

OPERATOR: R & B OIL & GAS, INC. PRODUCTION CSG: SIZE @ ' WITH SX

NAME AND PO BOX 422 SURFACE CASING: SIZE 8 5/8" @ 320' WITH SX

ADDRESS ATTICA, KS 67009

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR VONFELDT DRILLING, INC. LICENSE NUMBER 9431

ADDRESS PO BOX 611 RUSSELL, KS 67665-0611

COMPANY TO PLUG AT: HOUR: 5:30 PM DAY: 30 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM GREG DAVIDSON

(COMPANY NAME) VONFELDT DRILLING INC (PHONE) 785-483-6446

RECEIVED
STATE CORPORATION COMMISSION
SEP 08 2000
9-8-00
CONSERVATION DIVISION
Wichita, Kansas

WERE:

1ST PLUG AT 1460' WITH 50 SX CEMENT. 2ND PLUG AT 600' WITH 50 SX CEMENT.

3RD PLUG AT 350' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT. 5TH PLUG TO

CIRCULATE RAT HOLE WITH 15 SX CEMENT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 8:00 PM DAY: 30 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 1460' WITH 50 SX CEMENT. 2ND PLUG AT 600' WITH 50 SX CEMENT.

3RD PLUG AT 350' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT. 5TH PLUG TO

CIRCULATE RAT HOLE WITH 15 SX CEMENT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID NOT) OBSERVE THIS PLUGGING

INVOICED

DATE 9/11/00 SIGNED Stephen J. Pfeifer

WEL. NO. 2001060641

(TECHNICIAN)

FORM CP-213

[Handwritten signature]