

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

28

15-155-03113-0000
2-010065

API NUMBER: _____

S/2 SE, SECTION 36 TOWNSHIP 22 RANGE 4W

OPERATOR LICENSE # 4419 660 FEET FROM S SECTION LINE
1320 FEET FROM E SECTION LINE

OPERATOR BEAR PETROLEUM INC
NAME & BOX 438
ADDRESS HAYSVILLE KS 67060

LEASE NAME: BARTEL #2
COUNTY: RENO
WELL TOTAL DEPTH: 3342.5
PIPE: _____

108.65
RECEIVED
KANSAS CORPORATION COMMISSION
3-10-95
MAR 10 1995

SURFACE CASING: 12-1/2" @ 297'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SLD _____ D&A _____

CONSERVATION DIVISION
WICHITA, KS

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: GRESSELS OILFIELD SERVICE INC

ADDRESS: P O BOX 607, BURRTON KS 67020-0607 LICENSE: 3004

COMPANY TO PLUG AT: HOUR: 8:00 DAY: 8 MONTH: 2 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: DICK SCHREMMER

COMPANY NAME: BEAR PETROLEUM INC PHONE: 316-524-1225

WERE: SAND TO 3220' AND TOP W/7 SX CMT - SHOOT PIPE OFF @
600' - SPOT 50 SX CMT @ 600' - PULL PIPE TO 350' &
CIRC CMT TO SURF
OPEN HOLE 3276'-3342' - 7" CSG @ 3271'

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R. WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART () NONE (_____)

COMPLETED: HOUR: 11:00 DAY: 8 MONTH: 2 YEAR: 1995

ACTUAL PLUGGING REPORT:
SANDED TO 3200' & TOPPED W/7 SX CMT - SHOT PIPE OFF @
600' & PULLED - RAN 2-1/2" TUB TO 600' & SPOTTED 35 SX
CMT - PULLED TUB TO 350' & CIRC 230 SX CMT TO SURF
- RETRIVED 600' OF 7" & 5-1/2" CSG

REMARKS: USED 60/40 POZ W/4% GEL BY UNITED #1779

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson
Michael R. Wilson (AGENT)

FORM CP-2/3
REV. 3/90

INVOICED
DATE MAR 14 1995
INV. NO. 42355

Dev