

8-18

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-03116-00-00 Spot: C SWSESE  
Sec: 36 Twnshp & Dir: 22 S Rng & Dir: 4 W  
Feet: 330 frm N/S: S Feet: 990 frm E/W: E  
Lease/Unit Name: SIEMENS Well Number: 1  
County: RENO Total Vertical Depth: 3350 108.88 feet

Operator License No.: 7116  
Operator Name: Kantor Oil Company  
Address: 15 W. Sixth Street, STE 2601  
Tulsa, OK 74119

Conductor Pipe: Size feet:  
Surface Casing: Size 15.5 feet: 302  
Production: Size 8.625 feet: 3264

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/04/1999 9:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: Gressel Oilfield Service, Inc.  
Proposal Received from: Ed Gressel Company Name: Gressel Oilfield Service, Inc.  
OpRepPhoneNo: (316) 463-5161

Were: Sand to 3210' & top w/10 sacks cement. Perforate both strings of casing @ 575' & 375'. Run tubing to 575' & spot 50 sacks cement. Pull tubing to 375' & circulate cement to the surface. 8 5/8" casing @ 3264' 5 1/2" casing @ 2552' Open hole at 3264 to 3350

Plugging Proposal Received By: Dave Wertz, KCC Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/06/1999 3:30 PM

Actual Plugging Report:

Sanded to 3210' & topped with 7 sacks cement. Perforated both strings of casing @ 575' & 375'. Ran tubing to 580' and spotted 50 sacks cement. Pulled pipe to 372' & circulated 625 sacks of cement to the surface. Last 125 sacks of cement contained 1/4 pound flo-seal per sack.

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 18 1999  
8-18-99  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: Used 65/35 Pos mix w/6% gel by Copeland Acid & Cementing. Invoice # 19874  
Anhydrite Plug: No Bottom Plug: No Dakota Plug: No  
Plugged through:

I (did / did not) observe this plugging.  
INVOICED

Signed Michael Wilson  
(TECHNICIAN)

DATE 8-18-99  
INV. NO. 60240

