

12-2

2-

RECEIVED KANSAS CORPORATION COMMISSION

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

DEC 10 1993 12-10-93

CONSERVATION DIVISION

API NUMBER 15-155-20,141-0000

 NW NE SE , SECTION 36 TOWNSHIP 22 RANGE 4W

OPERATOR LICENSE # 6568 2310 FEET FROM S SECTION LINE
990 FEET FROM E SECTION LINE

OPERATOR KAISER-FRANCIS OIL CO
NAME & P O BOX 21468
ADDRESS TULSA OK 74121-1468

LEASE NAME: PETERS "B" #1
COUNTY: RENO DR 109.33
WELL TOTAL DEPTH: 3364' (3210')

CONDUCTOR PIPE: _____

SURFACE CASING: 10-3/4" @ 300'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SLD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: KAISER-FRANCIS OIL CO
ADDRESS: _____ LICENSE: _____

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 30 MONTH: 11 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: DEAN FRANKS
COMPANY NAME: KAISER FRANCIS PHONE: 316-463-3059

WERE: SET CIBP @ 3210' & TOP W/2 SX CMT - PERF 5-1/2" @
575' & SPOT 35 SX CMT - PERF 5-1/2" @ 350' & CIRC CMT
TO SURFACE
5-1/2" CSG @ PERFS 3255-3296'

PLUGGING PROPOSAL RECEIVED BY: MIKE WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 11:45 DAY: 2 MONTH: 12 YEAR: 1993

ACTUAL PLUGGING REPORT:

SET CIBP @ 3210' & TOPPED W/2 SX CMT - PERF 5-1/2" @
575' - RAN TUB & SET PACKER @ 561' - PUMPED 210 SX BUT
WELL DID NOT CIRC - BACKED OFF PKR & PUMPED 165 SX CMT
- HAD PARTIAL CIRCULATION - RAN TUB DWN 10-3/4" & 5-
1/2" ANNULUS & CIRC 165 SX CMT TO SURF - PUMPED
ADDITIONAL 90 SX CMT DWN 5-1/2" - ON 12/2/93, CMT IN 5-
1/2" HAD FALLEN 315' - TOPPED W/40 SX CMT

REMARKS: USED 60/40 POZ W/4% GEL ALLIED #3723 & #3725

INVOICED

I DID OBSERVE THIS PLUGGING.

DATE

DEC 14 1993

INV. NO.

39512

MICHAEL R WILSON

(AGENT)