

2 100189

35 P

API NUMBER 15-155-19152-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE NW, SEC. 20, T 22 S, R 7 WXX

_____ feet from S section line

_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9768

Lease Name Grover Well # A

Operator: R & D Oilfield Equipment

County Reno 116.51

Name & Address North Plains Oil Corporation

Well Total Depth 3585 feet

500 West 20th, #201

Conductor Pipe: Size 4 1/2 feet 3585

Hutchinson, KS 67502

Surface Casing: Size 8 5/8 feet 346

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____ Perf. 3552-66

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 Day: 8 Month: 4 Year: 19 87

Plugging proposal received from Milard Kelso

(company name) Kelso Casing Pulling (phone) 316-978-2457

were: Will plug according to the rules and regulations of the state of Kansas

Plugging Proposal Received by District #2 Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00 Day: 8 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT Sanded to 3500' and dumped four sacks cement. Shot and pulled 2800' of 4 1/2". Pumped three sacks hulls, 12 sacks gel, one plug and 125 sacks of cement. Shut in well.

Remarks: Allied #2010 60/40 poz 6% gel, Oper-700# SI - 400#
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-15-87

INV. NO. 16542

MAY 14 1987

Signed J. L. Sanders
(TECHNICIAN)