

24
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 8 1966

12-8-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Donald C. Slawson

Complete Address: 408 One-Twenty Bldg., Wichita, Kansas

Lease Name Lathrop "A" Well No. # 1

Location C NW SW Sec. 23 Twp. 24 Rge. 17 (E) (W)W

County Edwards Total Depth 4425'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 10:30AM Day 5th Month Dec. Year 1966

The Above well was plugged as follows:

258' of 8 5/8" surface pipe, cement circulated. 4424' of 4 1/2" long string,
cemented with 100 sacks. Top perferation 4368'. Bottom of the hole was sand-
ed to 4350', and cemented with 3 sacks, through the dump bailer. 3207' of
4 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid
to 250', rock bridge from 250' to 240', 5 sacks of cement was mixed in a
barrel, and put on plug at 240', through the dump bailer, and let set over
week end. Hole was bailed dry, and 20 sacks of cement was added to the plug.
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/9/66

INV. NO. 4415-u