

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
OCT 3 1966
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Donald C. Slawson

Complete Address: 408 One Twenty Bldg., Wichita, Kansas

Lease Name Wells "A" Well No. # 1

Location C SE NE Sec. 23 Twp. 24 Rge. 17 (E) (W) W

County Edwards Total Depth 4410'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Slawson Drilling Company, Inc.

Address: 408 One Twenty Bldg., Wichita, Kansas License No.

Operation Completed: Hour 5:45PM Day 29th Month Sept. Year 1966

The Above well was plugged as follows:

258' of 8 5/8" surface pipe, cement circulated. Hole was full of drilling mud. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to 240', and cemented with 35 sacks, through the drill pipe at 240'. Fluid in the hole was now at 35', 2nd cementing plug, bridged with 1/2 sack of hulls on fluid at 35', and cemented with 10 sacks to the base of the cellar. Rat hole bridged and cemented with 5 sacks.
This cementing was done by United Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlie Elving
Well Plugging Supervisor

DATE 10/3/66
INV. NO. 4026-W