

15-047-10061-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 22 1964

12-22-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name E. K. Edmiston

Complete Address: 501 First National Bank Bldg., Wichita, Kansas

Lease Name Hyter "B" Well No. # 1

Location C NW NE Sec. 25 Twp. 24 Rge. 16 (E) (W) W

County Edwards Total Depth 4320

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: E. K. Edmiston Drilling Company

Address: 501 First National Bank Bldg., Wichita, Kansas License No.

Operation Completed: Hour 9:30AM Day 21st Month Dec. Year 1964

The Above well was plugged as follows:

313' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fluid
in the hole was at 150'. 1st cementing plug and 1/2 sack of hulls was
pushed in fluid to 280', and cemented with 25 sacks, through the drill
pipe. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged solid with hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 12/23/64
INV. NO. 385-W

Signed: Archie Elving
Well Plugging Supervisor