


## DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission  
 Conservation Division  
 800 Bitting Building  
 Wichita, Kansas

FILE NO. 119-29LOCATION SW-SW-NWSEC. 27 TWP. 24 RGE. 16 WDry Hole  Abandoned Oil Well  Abandoned Gas Well 

I have this date completed supervision of plugging of:

Well No. 1 Lease FisherOperator Bramine & Holl Address 6427 E. Kellogg Wichita, Ks.Field \_\_\_\_\_ County EdwardsTotal Depth 4450 Feet.Plugging Contractor West Supply Co. Inc.Plugging Contractor's License No. 14Address Chase, Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 7/8" @ 300' c.w.c. 5 1/2" casing set  
4425' w/ 175 st cem. Cement drilled out to 4400'  
top perf 4268'. Sanded hole to 4250' dumped 5 st  
cem. shot off and pulled 5 1/2" casing. Filled  
hole with heavy mud to 300' set rock bridge  
and dumped 20 st cem. mud to 35' rock  
bridge and 10 st cem. to base of cellar

**RECEIVED**  
 STATE CORPORATION COMMISSION

6-7-55

JUN 7 - 1955

CONSERVATION DIVISION  
 Wichita, Ks.

Warren H. Horner  
 District Conservation Agent

Date June 4, 1955

**PLUGGING**  
 FILE SEC 27-24-R-16W  
 BOOK PAGE 119 LINE 29