

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JUN 29 1979

6-29-79  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Armstong & Jackman

Complete Address R.R. #1 Leon, Ks. 67074

Lease Name Meyer "B" Well No. 1

Location E/2 E/2 SE Sec. 33 Twp. 24 Rge. 16 (E) (W) W

County Edwards Total Depth 4420

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 1:30 Pm. Day 26 Month 6 Year 1979

The above well was plugged as follows:

328' 8 5/8" casing w/250 sax cement. 4 1/2" casing set at 4419' w/100  
sax cement. Preforations at 4318' to 4324'-4324' to 4334'-4370' to 4380'  
Allied mixed & pumped 50 sax common cement in 4 1/2" casing, top at 4104'  
Shut in w/ 2000# Pressure. Pull 3605' casing. Allied mixed & pumped 8  
sax hulls-25 sax gel- Release plug-Mixed & pumped 125 sax 50/50 posmix  
cement w/ 4% gel & 3% cc to top of casing. Shut in w/200# pressure.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: [Signature]  
Well Plugging Supervisor

DATE 7-2-79

INV. NO. 9926-W