

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-21895-00-00

Spot: S2N2S2NE

Sec/Twnshp/Rgc: 9-34S-41W

1720 feet from N Section Line, 1320 feet from E Section Line

Lease Name: KRIEGER A

Well #: 2

County: MORTON

Total Vertical Depth: 3750 feet

Operator License No.: 33136

Op Name: ANADARKO E & P ONSHORE LLC

Address: PO BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2835		WITH 10 SX CMT
PROD	5.5	3750	632	WITH 625 SX CMT
SURF	8.625	675		WITH 505 SX CMT

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 11/04/2015 10:30 AM

Plug Co. License No.: 33338

Plug Co. Name: ORR ENTERPRISES, INC.

Proposal Rcvd. from: RONNIE ORR

Company: ORR ENTERPRISES, INC.

Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 2836' WITH 10 SX CMT. PLUG AT 1450' WITH 30 SX CMT. PLUG AT 800' WITH 50 SX CMT. PLUG AT 360' WITH 40 SX CMT. PLUG AT 64' WITH 20 SX CMT.

Plugging Proposal Received By: WADE KLAUS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 11/04/2015 5:30 PM

KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 2835' WITH 10 SX CMT. 1ST PLUG AT 1449' WITH 30 SX CMT. 2ND PLUG AT 800' WITH 50 SX CMT. 3RD PLUG AT 360' WITH 40 SX CMT. 4TH PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3176	3184		
3153	3160		
3114	3119		
3061	3065		
2932	2939		
2907	2912		
2898	2903		
2886	3184		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed



12/18/15
CKM

RECEIVED
NOV 17 2015
KCC DODGE CITY

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION Form CP-2/3

DEC 04 2015
CONSERVATION DIVISION
WICHITA, KS