

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-145-21476-00-00  
Spot: SESESE Sec/Twnshp/Rge: 15-20S-20W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease Name: DICK Well #: 1-15  
County: PAWNEE Total Vertical Depth: 2490 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2480	0	WITH 125 SX CMT
SURF	8.625	488		WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/10/2015 2:45 PM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: \_\_\_\_\_ Phone: (316) 524-1225

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: NONE  
Date/Time Plugging Completed: 09/10/2015 4:45 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PUMP 30 SX CMT WITH 100# HULLS. DISPLACE TO 2200'. SHUT IN WITH 200#. PERFORATE AT 1337'. PUMP 40 SX CMT DISPLACE TO 1100'. WAIT 1 HOUR & TAG PLUG AT 1230'. PERFORATE AT 538'. CIRCULATE CMT TO SURFACE WITH 200 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2256	2270		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

12/18/15  
ckm

District: 01

Signed \_\_\_\_\_

  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

DEC 09 2015

CONSERVATION DIVISION  
WICHITA, KS

RECEIVED  
DEC - 3 2015  
KCC DODGE CITY