

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-10148-00-00
Spot: NESENWSE Sec/Twnshp/Rge: 23-30S-17W
1884 feet from S Section Line, 1473 feet from E Section Line
Lease Name: RUNNYMEDE UNIT B Well #: 1-23
County: KIOWA Total Vertical Depth: 4955 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4863		WITH 2 SX CMT
PROD	4.5	4953	2416	WITH 125 SX CMT
SURF	8.625	523		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/04/2015 8:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 4873' WITH 2 SX CMT. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 573' WITH 50 SX CMT. PLUG AT 330' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: WADE KLAUS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/04/2015 10:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4863' WITH 2 SX CMT. 1ST PLUG AT 1014' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 553' WITH 50 SX CMT. 3RD PLUG AT 338' WITH 50 SX CMT. 4TH PLUG AT 61' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4931	4935		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed [Signature]

JA

(TECHNICIAN)

KCC WICHITA

Form CP-2/3

RECEIVED
DEC - 8 2015
KCC DODGE CITY

DEC 11 2015

RECEIVED

12-11-2015

12/18/15
CKM