

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-22646-00-00
Spot: NWSWNENE Sec/Twnshp/Rge: 12-27S-12E
4345 feet from S Section Line, 1140 feet from E Section Line
Lease Name: LATHAM Well #: 14
County: GREENWOOD Total Vertical Depth: 1741 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2761		276 SX
SURF	7.625	41		20 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/07/2015 8:00 AM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Rcvd. from: MATT OSBORN Company: _____ Phone: (620) 583-2257

Proposed Plugging Method: Per KCC Instructions, bullhead squeeze.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: NONE
Date/Time Plugging Completed: 12/07/2015 10:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

connect to casing, pumped 25 sxs cement @ 1741', pumped 5 sxs cement @ 1000', pumped 20 sxs cement 250' to surface, gel spacers & cotton seed hulls between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1638	1650		
RECEIVED KCC DIST # 3 DEC 14 2015 CHANUTE, KS MH			

Remarks:

Plugged through: CSG

12/18/15
CKM

District: 03

Signed Mike Heffern
(TECHNICIAN)

KCC WICHITA

DEC 16 2015

RECEIVED

8.00

15-073-22646-0000

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



Cement or Acid Field Report
Ticket No. **2644**
Foreman Rick Leford
Camp Eureka KS

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
12-7-15	1031	LATHAM # 14	12	27	12	GW	KS
Customer	Mailing Address	City	State	Zip Code	Safety Meeting	Unit #	Driver
Daystar Petroleum Inc.	522 N. Main	Eureka	KS	67045	RL DG ES AB	105	Dave G.
						110	Ed S.
						145	Allen B.

Job Type P.Z.A Hole Depth 1748' Slurry Vol. 13851 Tubing _____
 Casing Depth _____ Hole Size _____ Slurry Wt. 14# Drill Pipe _____
 Casing Size & Wt. 4 1/2" Cement Left in Casing _____ Water Gal/SK 7.0 Other Puffs @ 1638-50
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting - Rig up to 4 1/2" casing. Plugging orders as follows
25 SKS on bottom
5 SKS @ 1000'
20 SKS @ 250' to surface

"THANK YOU"

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	550.00	550.00
C107	10	Mileage 2nd well	3.95	39.50
C203	50 SKS	60/40 Pozmix cement	12.75	637.50
C206	170#	40% gel	.20	34.00
C206	200#	gel spacers	.20	40.00
C214	25#	hulls	.45	11.25
C102A	2.15	tan mileage bulk TRK	m/c	200.00
C113	2 hrs	80 Bbl vac. TRK	85.00	170.00
KCC WICHITA				
DEC 16 2015				
RECEIVED				
			Subtotal	1682.25
			Sales Tax	

Authorization Witnessed by Jason Title Co. Rep Total _____

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.