

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-22680-00-00
Spot: SWSESENE Sec/Twnshp/Rge: 12-27S-12E
2805 feet from S Section Line, 495 feet from E Section Line
Lease Name: LATHAM Well #: 23
County: GREENWOOD Total Vertical Depth: 1728 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1720		253 SX
SURF	7.625	41		17 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/08/2015 8:00 AM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Rcvd. from: MATT OSBORN Company: _____ Phone: (620) 583-5527

Proposed Plugging Method: Per KCC Instructions, bullhead squeeze.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/08/2015 9:30 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

connect to casing ,pumped 25 sxs cement @ 1728',pumped 5 sxs cement @ 600' , pumped 20 sxs cement 250' to surface,gel spacers between cement plugs,cotton seed hulls in bottom plug.

Perfs:

Top	Bot	Thru	Comments
1632	1639		
RECEIVED KCC DIST # 3 DEC 14 2015 CHANUTE, KS MH			

Remarks:

Plugged through: CSG

12/18/15
CPM

District: 03

Signed Mico [Signature]
(TECHNICIAN)

KCC WICHITA
DEC 16 2015
RECEIVED

15-073-22680 0000

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



Cement or Acid Field Report
Ticket No. 2661
Foreman Rick Laddard
Camp Eureka KS

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
12-8-15	1031	LATHAM # 23	12	27	12	GW	KS
Customer	Mailing Address	City	State	Zip Code	Safety Meeting	Unit #	Driver
Daystar Petroleum Inc.	522 N. Main	Eureka	KS	67045	26 OG JF AB	105	Dave C.
						113	Shannon F.
						145	Allen B.

Job Type P. GA Hole Depth _____ Slurry Vol. 13 bbl Tubing _____
 Casing Depth _____ Hole Size _____ Slurry Wt. 14 # Drill Pipe _____
 Casing Size & Wt. 4 1/2" Cement Left in Casing _____ Water Gal/SK 7" Other Puffs @ 1632-39
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting - Rig up to 4 1/2" casing. Plugging orders as follows:

25 sks on bottom
5 sks @ 600'
20 sks @ 250' to surface

"THANK YOU"

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	550.00	550.00
C107	10	Mileage 10 th well	3.95	39.50
C203	50 sks	(60) 40 Pozmix cement	12.75	637.50
C206	170 #	4% gel	.20	34.00
C206	200 #	gel-spacers	.20	40.00
C214	25 #	balls	.45	11.25
C102A	2.15	ten mileage bulk truck	m/l	200.00
C113	2 hrs	80 Bbl vac. rx	85.00	170.00
KCC WIP				
DEC 16 2015				
RECEIVED				
			Subtotal	1182.25
			Sales Tax	

Authorization Witnessed by Jison Title Collyer Total _____

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.