

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-22738-00-00  
Spot: N2S2 Sec/Twnshp/Rge: 30-19S-12W  
1980 feet from S Section Line, 2640 feet from E Section Line  
Lease Name: DOONAN Well #: 3-A  
County: BARTON Total Vertical Depth: 3415 feet

Operator License No.: 7054  
Op Name: DOONAN AND SONS, INC.  
Address: PO BOX 1466  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3380		125 SX
SURF	8.625	300		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/20/2015 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: RON KELSO Company: DOONEN AND SONS, INC. Phone: (620) 793-3563

Proposed  
Plugging  
Method:

Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls and 15 sx gel.

Plugging Proposal Received By: BRUCE RODIE  
Date/Time Plugging Completed: 11/20/2015 1:00 PM

WitnessType: COMPLETE (100%)  
KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350', 630' and 275'. Ran tubing to 3370' and pumped 15 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1400' and pumped 75 sx cement w/100 hulls. Pulled tubing to 600'. Circulated cement to surface on casing and surface pipe with 130 sx cement and 100 # hulls. Pulled tubing and topped off with 25 sx cement.

GPS: 38.36663 -098.69112

Perfs:

Top	Bot	Thru	Comments
3380	3415		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed

*Bruce Rodie*

(TECHNICIAN)

12/18/15 ckm

CM

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

DEC 09 2015

CONSERVATION DIVISION  
WICHITA, KS