

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-11213-00-00  
Spot: SWNESENE Sec/Twnshp/Rge: 11-35S-2E  
3614 feet from S Section Line, 350 feet from E Section Line  
Lease Name: ANDERSON-WOODS Well #: 4  
County: SUMNER Total Vertical Depth: 3550 feet

Operator License No.: 32887  
Op Name: ENDEAVOR ENERGY RESOURCES, LP  
Address: 110 N MARIENFELD, STE 200  
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3450		
PROD	5.5	3504		60 SX
SURF	8.625	179		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/26/2015 10:00 AM  
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC  
Proposal Rcvd. from: JOE DRISKILL Company: ENDEAVOR ENERGY RESOURCES, Phone: (918)467-3111

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/16/2015 10:00 AM KCC Agent: DAN FOX

Actual Plugging Report:

BRIDGE PLUG SET @ 3450' ABOVE THE BARTLESVILLE. CIBP SET @ 3100' CAPPED W/2 SX. SHOT PERFS. AT 250', RAN IN 2 3/8" TUBING TO 280' PUMPED IN 125 SX OF 60/40 POS. MIX WITH 4% GEL. PULLED TUBING AND CEMENT WAS SLOWLY DROPPING. CAME BACK AND TOP PLUG HAD DROPPED OUT OF SITE AND SO WENT BACK DOWN WITH TUBING AND PUMPED AN ADDITIONAL 115 SX. NO MORE DROP. CUT OFF SURFACE CASING BELOW GROUND LEVEL. PLUGGING COMPLETE. ELITE CEMENTING TICKET #2541.

Perfs:

Top	Bot	Thru	Comments
3486	3491	TBG	
3129	3141	TBG	

Remarks: PLUGGING OF WELL IS A RESULT OF A COMPLIANCE AGREEMENT BETWEEN OPERATOR AND COMMISSION, DOCKET #15-CONS-442-CMSC.

Plugged through: TBG

District: 02

Signed Daniel Z. Fox  
(TECHNICIAN)

12/18/15 ckm

KCC WICHITA

DEC 15 2015

RECEIVED