

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-11371-00-00
Spot: SENENE Sec/Twnshp/Rge: 2-35S-2E
4290 feet from S Section Line, 330 feet from E Section Line
Lease Name: HOMESTEAD Well #: 1
County: SUMNER Total Vertical Depth: 3530 feet

Operator License No.: 32887
Op Name: ENDEAVOR ENERGY RESOURCES, LP
Address: 110 N MARIENFELD, STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3539		0 SX
SURF	8.625	105		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/26/2015 8:00 AM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Rcvd. from: JOE DRISKILL Company: ENDEAVOR ENERGY RESOURCES, Phone: (918) 467-3111

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 09/18/2015 12:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

CIBP SET @ 3450'. CAPPED WITH 2 SX. SHOT PERFS. @ 251'. RAN IN 2 3/8" TUBING TO 280' PUMPED 125 SX OF 60/40 POS. MIX WITH 4% GEL. PULLED TUBING AND TOPPED OFF CSG WITH 15 SX. CAME BACK AND CUT OFF SURFACE CASING BELOW GROUND LEVEL. PLUGGING COMPLETE. ELITE CEMENTING TICKET #2544.

Perfs:

Top	Bot	Thru	Comments
3509	3515	TBG	

Remarks: PLUGGING OF WELL IS A RESULT OF A COMPLIANCE AGREEMENT BETWEEN OPERATOR AND COMMISSION, DOCKET #15-CONS-442-CMSC.

Plugged through: TBG

*12/18/15
AKM*

District: 02

Signed _____

Daniel F. Fox
(TECHNICIAN)

KCC WICHITA

DEC 15 2015

RECEIVED